BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2017-18/OW/WORK_INDENT29488

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/24/2017-18, Date: 21.02.2018

Maintenance of Existing Borewells at Hegadenagara Surrounding area in Ward No. 06 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Madhuraj H N	
				In Figures	In Words
1	2800	Labour Charges of lifting of non functioning submersible Pump set along with cable and GI Pipes (BWSSB SR 14-15, P-558 I-1(i)	Each	104	Rupees One Hundred Four Only
2	40	Transportation of pumping machineries (P. 56 / I. 10.3.19) PRED SR (2012-13)	Each	900	Rupees Nine Hundred Only
3	8	Rewinding of Submersible Pump Sets 10 HP	No	4785	Rupees Four Thousand Seven Hundred Eighty Five Only
4	10	7.5 HP	No	3822	Rupees Three Thousand Eight Hundred Twenty Two Only
5	10	12.5 HP	No	5885	Rupees Five Thousand Eight Hundred Eighty Five Only
6	12	15.0 HP	No	5800	Rupees Five Thousand Eight Hundred Only
7	210	Pump Bowls (BWSSB SR 14-15 P-58 I-B)	No	308	Rupees Three Hundred Eight Only
8	40	Intermediate Piece (I.P) With IP Leaded Bronxe bush (BWSSB SR 14-15 P-58 I-B2)	No	715	Rupees Seven Hundred Fifteen Only
9	40	Upper Flange (BWSSB SR 14-15 P-59 I-C3)	No	330	Rupees Three Hundred Thirty Only
10	40	Lower Housing (BWSSB SR 14-15 P-59 I-C4)	No	539	Rupees Five Hundred Thirty Nine Only
11	150	Guide vane (BWSSB SR 14-15 P-58 I-B5)	No	192	Rupees One Hundred Ninety Two Only
12	40	Impeller Shell moulded with aluminium Bronze) (BWSSB SR 14-15 P-58 I-B6)	No	264	Rupees Two Hundred Sixty Four Only
13	60	Discharge outlet (D.O) Bearing D.O Steel Bush P. (BWSSB SR 14-15 P-58 I-B7)	No	522	Rupees Five Hundred Twenty Two Only
14	35	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) (BWSSB SR 14-15 P-58 I-B10)	No	660	Rupees Six Hundred Sixty Only
15	40	Pump Couping (Stainless Steel) (BWSSB SR 14-15 P-58 I-B12)	No	341	Rupees Three Hundred Forty One Only
16	100	Stud and Nuts (BWSSB SR 14-15 P-59 I-C8)	Each	88	Rupees Eighty Eight Only
17	25	Motor Base With Pin (BWSSB SR 14-15 P-59 I-C11)	Each	407	Rupees Four Hundred Seven Only
18	20	Starter (with one year Guarantee) P No. 55 / I No. 10.3.3 PRED SR (2012-13)	No	5050	Rupees Five Thousand Fifty Only
19	25	Rotor (with one year Guarantee) P No. 55 / I No. 10.3.6) PRED SR (2012-13)	No	4700	Rupees Four Thousand Seven Hundred Only
20	40	Carbon Housing P. No. 56 / I No.10.3.12 PRED SR (2012-13)	No	475	Rupees Four Hundred Seventy Five Only
21	45	Thrust bearing block assembly complete with Segment bearing pad.P. No. 55 / I No.10.3.13 PRED SR (2012-13)	No	1150	Rupees One Thousand One Hundred Fifty Only
22	40	Oil Seal P. No. 54 / I No.10.2.3 PRED SR (2012-13)	No	125	Rupees One Hundred Twenty Five Only
23	40	Oil Seal Steel Bush P. No. 54 / I No. 10.2.4 PRED SR (2012-13)	No	150	Rupees One Hundred Fifty Only
24	60	D.O Bearing P. No. 44 / I No. 10.2.7 PRED SR (2012-13)	No	285	Rupees Two Hundred Eighty Five Only
25	300	Steel Bush P. No.55 / I No. 10.2.9 PRED SR (2012-13)	No	150	Rupees One Hundred Fifty Only
26	140	Allen Screw P. No.44 / I No. 10.2.9 RDPR SR (2012-13)	No	25	Rupees Twenty Five Only
27	30	Pump Key (Stainless Steel) P. No. 45 / I No. 10.2.11 RDED SR (2012-13)	No	125	Rupees One Hundred Twenty Five Only

Signature of the contractor Madhuraj H N

16/02

Executive Engineer

16/02

o.	Approved Qty.	Description	Unit	Approved Tender Rates of Madhuraj H N	
				In Figures	In Words
28	20	Non – return valve (NRV) assembly complete with rubber 'O' Ring P. No. 55 / I No. 10.2.14 PRED SR (2012-13)	No	1350	Rupees One Thousand Three Hundred Fifty Only
29	40	Cable Guard P. No. 55 / I No. 10.2.15 PRED SR (2012-13)	No	150	Rupees One Hundred Fifty Only
30	40	Strainer P. No. 45 / I No. 10.2.15 RDED SR (2012-13)	No	150	Rupees One Hundred Fifty Only
31	40	Brass Filter P. No. 55 / I No. 10.2.17 PRED SR (2012-13)	No	250	Rupees Two Hundred Fifty Only
32	40	Labour Chargesw (Over Hauling Only) P. No. 45 / I No. 10.2.18 PRED SR (2012-13)	No	556	Rupees Five Hundred Fifty Six Only
33	40	Re-erection charges of pumping machineries including overhauling and pointing P. No. 56 / I No. 10.3.20 PRED SR (2012-13)	Each	950	Rupees Nine Hundred Fifty Only
34	55	Lock Ring P. No. 45 / I No. 10.3.11 PREC SR (2012-13)	Each	85	Rupees Eighty Five Only
35	40	a) Carbon Housing P. No. 46 / I No. 10.3.12 APRDED SR (2012-13)	Each	475	Rupees Four Hundred Seventy Five Only
36	40	Top Carbon/Ferrodo padding P. No. 46 / I No. 10.3.12 APRDED SR (2012-13)	Each	150	Rupees One Hundred Fifty Only
37	35	Bearing (Gunmetal) Centrifugal) Cast Aluminium Bronxe, Beaing bush P. No. 46 / I No. 10.3.16 APRDED SR (2012-13)	Each	400	Rupees Four Hundred Only
38	60	Circillps P. No. 45 / I No. 10.3.17 PREC SR (2012-13)	Each	50	Rupees Fifty Only
39	500	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts. P. No. 49/ I No. 29-b(1) 4 Sqm mm of 56 strands 0.3mm dia Group - A KPWD Electrical SR 2010-11	Mtr	185	Rupees One Hundred Eighty Five Only
40	55	Supplying and fixing miniature circuit breakers/isolators in existing MCB distribution boards using necessary fixing materials and wiring complete as required, 40 to 63 Amps DP (P.NO - 526, I.NO - 13D (a), BWSSB SR 13-14)	No	906	Rupees Nine Hundred Six Only
41	165	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete.... P No. 32/I No 3b KPWD Electrical SR 2010-11	No	150	Rupees One Hundred Fifty Only
42	30	Supplying & delivery of brand new best make non return valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark (50mm Gate wheel Valve. (PWD SR 2015-16, P.NO.XXIV, Sl.no, 673)	No	1727.49	Rupees One Thousand Seven Hundred Twenty Seven and Forty Nine Paise Only
43	60	Providing and fixing of 50mm GI bend to motor (PWD SR 2016-17, P.NO.XXXVIII GI FITTINGS TABLE)	No	228.73	Rupees Two Hundred Twenty Eight and Seventy Three Paise Only
44	60	Providing and fixing of 50mm GI Nipple to motor (PWD SR 2016-17, P.NO.XXXVIII GI FITTINGS TABLE)	No	108.58	Rupees One Hundred Eight and Fifty Eight Paise Only
45	60	Providing and fixing of 50mm GI union to the motor ((PWD SR 2016-17, P.NO.XXXVIII GI FITTINGS TABLE)	No	234.07	Rupees Two Hundred Thirty Four and Seven Paise Only
46	185.63	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications (P.NO - 5, I.NO - 2.3, PWD SR 16-17)	Cum	133.5	Rupees One Hundred Thirty Three and Fifty Paise Only
47	550	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete (P.NO - 94, I.NO - 13.73.2, PWD SR 16-17)	Mtr	356	Rupees Three Hundred Fifty Six Only

Signature of the contractor Madhuraj H N

16/07
Executive Engineer

16/07

No.	Approved Qty.	Description	Unit	Approved Tender Rates of Madhuraj H N	
				In Figures	In Words
48	185.63	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications (P.NO - 6, I.NO - 2.11, PWD SR 16-17)	Cum	35.6	Rupees Thirty Five and Sixty Paise Only
49	16	KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6/13.3 P. 97 / I.13.37 PWD SR - 2016-17	Each	2148.46	Rupees Two Thousand One Hundred Forty Eight and Forty Six Paise Only
50	3500	Threading of GI Pipes 50mm Dia P. No. 15 / I No.3.11.6 PRED SR (2012-13)	No	25	Rupees Twenty Five Only

Madhuraj HN

Signature of the Contractor

16/07

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

16/07